

# CONSTRUCTION NOTICE

## SEWER WORK WILL BEGIN ON:

**MONDAY, OCT. 14 & TUESDAY, OCT. 15**  
**4 P.M. TO 12 A.M. - CHERRIX AVENUE**

The EDGEWATER PARK SEWER AGE AUTHORITY has contracted **Vortex Services** for sewer rehabilitation work in your area. Vortex will be using “trenchless” technology to renew aging sewers **without the need to excavate**, which means less mess, less disruption and less time spent on your street compared to traditional digging and replacing. During this process, commonly called cured-in-place pipe (CIPP) lining, a flexible felt material is saturated with a two-part resin and is installed inside the existing sewer pipe. Once installed, the felt tube is cured by introducing steam throughout the sewer line, which hardens and becomes a new sewer within the existing deteriorated sewer.

Prior to the liner being installed, the sewer is cleaning using high-pressure water jetting. You may notice bubbling in your toilets during this process.

During the liner installation process, your home's sewer connection that flows out into the street will be temporarily blocked. **To prevent wastewater from backing up into your home or business, please avoid doing laundry, running the dishwasher, taking long showers/baths, or flushing the toilet multiple times.** Your water will not be shut off, but we respectfully ask that you avoid using large quantities of water, as it will have nowhere to go while the liner is being cured. Once the liner is properly cured, your lateral connection will be re-opened and you may resume using water as normal.

During the lining process, you may also notice a glue-like smell near the work zone, which is non-toxic and will dissipate once windows are opened and fresh air is introduced. Please observe and obey any no parking signs and beware of any traffic pattern changes in the area. Roads may be temporarily closed off and detoured during construction.

If you have any questions, please do not hesitate to ask for the on-site supervisor. Vortex also maintains a 24-hour emergency telephone number at 732-625-9300.

**Lining Foreman: Dan Linen 347-782-3533**  
**Project Manager: Cory Twibell 516-698-2194**

